

18681 Lake Drive East Chanhassen, MN 55317 952-607-6512 www.rpbcwd.org

### **Riley Purgatory Bluff Creek Watershed District Permit Application Review**

### Permit No: 2024-077

Considered at Board of Managers Meeting: November 6, 2024

**Project Procedural History:** Permit application 2020-051 for the BIOLYPH parking-lot expansion was conditionally approved May 5, 2021. Because the conditions of approval for the proposed work were not complete prior the expiration date, no work was conducted and the conditional approval expired May 5, 2022. The applicant has submitted a new permit application for the same work.

### Received complete: September 24, 2024

Applicant:	BIOLYPH, Timothy Pearcy
Consultant:	Sambatek, Inc., Brady Busselman
Project:	BIOLYPH Parking Lot Expansion –a parking lot expansion at an existing medical facility in
	Chaska. Stormwater management facilities include an underground filtration system
	combined with rainwater harvest and reuse system to provide volume control, water
	quality, and rate control.
Location:	4275 Norex Drive, Chaska, MN 55318
<b>Reviewer:</b>	Scott Sobiech P.E., Barr Engineering

### **Board Action**

Manager \_\_\_\_\_\_ moved and Manager \_\_\_\_\_\_ seconded adoption of the following resolutions based on the permit report that follows and the presentation of the matter at the November 6, 2024 meeting of the managers:

Resolved that the application for Permit 2024-077 is approved, subject to the conditions and stipulations set forth in the Recommendations section of the attached report.

Resolved that on determination by the RPBCWD administrator that the conditions of approval have been affirmatively resolved, the RPBCWD president or administrator is authorized and directed to sign and deliver Permit 2024-077 to the applicant on behalf of RPBCWD.

Upon roll call vote, the resolutions were adopted, \_\_\_\_\_

### Applicable Rule Conformance Summary

Rule	Issue		Conforms to RPBCWD Rules?	Comments
С	Erosion Control Plan		See Comment	See rule-specific permit condition C1 related to person responsible for erosion control during construction.
J	Stormwater	Rate	Yes	
	Management	Volume	Yes	
		Water Quality	Yes	
		Low Floor Elev.	Yes	
		Maintenance	See Comment	See rule-specific permit condition J1 related to recordation of stormwater facility maintenance declaration.
		Chloride Management	See Comment	See stipulation #4
		Wetland Protection	Yes	
L	Permit Fee Deposit		Yes	\$3,000 received September 26, 2024. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. As of October 28, 2024 the amount due is \$1,272.
М	Financial Assurances		See Comment	The financial assurance is calculated at \$523,516

### Background

Permit 2020-051 for the proposed land-disturbing activities was conditionally approved May 5, 2021. Because the conditions of approval for the proposed work were not met, the permit was not issued and in May 2021 the conditional approval expired. The applicant did not commence proposed work. Under Rule A, subsection 5, the applicant must reapply for a permit from the District.

The applicant proposes construction of Phase I of the site redevelopment which entails the expansion of an existing parking lot for a medical building resulting in 0.55 acres of new or fully redeveloped impervious area. The project proposes construction of an underground filtration system combined with rainwater harvest and reuse system to provide stormwater quality, volume, and rate control. Runoff leaving the underground filtration system will be conveyed to either reuse storage tanks or an existing, on-site storm sewer. The existing storm sewer conveys runoff directly into a wetland in the northwest corner of the site. Because the wetland will not be disturbed and does not receive direct overland flow from the proposed land disturbing activities, the engineer judges that the wetland edge is not "downgradient" from the land-disturbing activities, and therefore the RPBCWD buffer requirements do not apply to the proposed project. As part of the prior submittal under 2020-051, the applicant provided big picture proof of concept information for the full build-out condition of phase 1 (parking lot expansion) and phase 2 (a 26,000 square foot building expansion) to gauge whether the final project would be able to achieve compliance with the RPBCWD regulatory program. The full build-out of the site is anticipated to take several years. No work beyond the presently proposed parking-lot expansion (phase 1) will be authorized by this permit, if issued. The property owner must submit a separate permit application for any further work with necessary supporting materials showing compliance of the proposed work with applicable RPBCWD regulatory requirements applicable at the time of submission. In addition, the common scheme of development framework in subsection 2.5 of Rule J will apply to build-out of the properties. RPBCWD's approval, if granted, of this permit 2024-077 does not represent a determination of compliance of the ultimate build-out condition with RPBCWD regulatory requirements. The data for the ultimate development in this report are provided for information only.

Project Site Information	Phase 1	Phase 1 and Phase 2
Total Site Area (acres)	13.59	13.59
Existing Impervious (acres)	3.08	3.08
Disturbed Impervious Area (acres)	0.03 (<1%)	0.03 (<1%)
Proposed Impervious Area (acres)	3.60	4.20
Additional Impervious Area (acres)	0.52 (17% increase)	1.12 (36% aggregate increase)
Regulated Impervious Area(acres)	0.55	1.15
Total Disturbed Area (acres)	0.69	1.64

The following materials were reviewed in support of the permit request:

- 1. Permit Application received September 24, 2024
- 2. Stormwater Management Report dated September 24, 2024
- 3. Project Plan Set (10 sheets) dated September 24, 2024
- 4. Geotechnical Evaluation Report by Northern Technologies, LLC dated June 5, 2014
- 5. Electronic HydroCAD models received on September 24, 2024
- 6. HydroCAD Output Drainage Summary Tables received on September 24, 2024
- 7. MIDS model Output Summary Tables received on September 24, 2024
- 8. Electronic MIDs model received on September 24, 2024
- 9. Stormwater BMP Opinion of Probable Cost dated October 11, 2024
- 10. Irrigation area plan received on September 24, 2024
- 11. Chloride Management Plan received on September 24, 2024 (unsigned)

- 12. P8 water quality model received October 11, 2024.
- 13. Response to comments received October 11, 2024

### **Rule Specific Permit Conditions**

### **Rule C: Erosion Prevention and Sediment Control**

Because the applicant proposes to alter 0.69 acres of land-surface area, the project must conform to the requirements in the RPBCWD Erosion and Sediment Control rule (Rule C, Subsection 2.1).

The erosion and sediment control plans prepared by Sambatek include installation of perimeter control, inlet protection for storm sewer catch basins, a rock construction entrance, protection of stormwater management facilities, placement of a minimum of 6 inches of topsoil, decompaction of pervious areas compacted during construction, and retention of native topsoil onsite.

To conform to RPBCWD Rule C requirements the following revisions are needed:

C1. The Applicant must provide the name and contact information of the general contractor responsible for the site. RPBCWD must be notified if the responsible party changes during the permit term. This information is required prior to issuance of the permit.

### **Rule J: Stormwater Management**

Because the applicant proposes 0.69 acres of land-disturbing activity, the project must meet the criteria of RPBCWD's Stormwater Management rule (Rule J, Subsection 2.1). The criteria listed in Subsection 3.1 will apply to only to the disturbed area because the project will disturb less than 50% of the existing impervious surface on the parcel and will not increase imperviousness of the parcel by more than 50 percent (Rule J, Subsection 2.3).

The applicant proposes construction of an underground filtration system combined with a rainwater harvest and reuse system to provide stormwater quantity, volume and rate quality control. The underground filtration system will discharge treated and untreated runoff to underground storage tanks to be used for irrigation.

### Rate Control

In order to meet the rate control criteria listed in Subsection 3.1.a, the 2-, 10-, and 100-year post development peak runoff rates must be equal to or less than the existing discharge rates at all locations where stormwater leaves the site. The Applicant used a HydroCAD hydrologic model to simulate runoff rates for pre- and post-development conditions for the 2-, 10-, and 100-year frequency storm events using a nested rainfall distribution, and a 100-year frequency, 10-day snowmelt event. The existing and proposed 2-, 10-, and 100-year frequency discharges from the site are summarized in the table below.

Modeled Discharge Location	2-Year Discharge (cfs)		10-\ Dischar	-Year 100 arge (cfs) Discha		100-Year Discharge (cfs)		10-Day Snowmelt (cfs)	
	Ex	Prop	Ex	Prop	Ex	Prop	Ex	Prop	
To Wetland	27.3	25.9	47.4	44.3	92.7	89.8	1.9	1.8	
Southwest	3.6	3.6	6.5	6.5	13.2	13.2	0.3	0.3	
Northeast	5.3	5.3	10.0	9.9	21.0	20.9	0.4	0.4	

The proposed stormwater management plan will provide rate control in compliance with the RPBCWD requirements for the 2-, 10-, and 100-year events. Thus, the proposed project meets the rate control requirements in Rule J, Subsection 3.1a.

### Volume Abstraction

Subsection 3.1.b of Rule J requires the abstraction onsite of 1.1 inches of runoff from the new and disturbed impervious surface of the parcel. An abstraction volume of 2,200 cubic feet is required from the 0.55 acres (24,004 square feet) of regulated impervious area for phase 1 of the project for volume retention. The Applicant proposes a rainwater harvest and reuse system to provide volume abstraction. Pretreatment is provided by sump manholes at all discharge locations into the underground facility (Rule J, Subsection 3.1.b.1).

The proposed reuse system consists of two 20,000-gallon underground storage tanks for a total of 40,000 gallons (or 5,347 cubic feet) of rainwater harvest and reuse storage volume. The applicant proposes to reuse the rainwater by irrigating 2.2 acres of pervious area with the existing, on-site irrigation system. The table below summarizes the volume abstraction required and the volume abstraction achieved by the proposed stormwater management facility on site. The engineer concurs with the modeling, and finds that the proposed project is in conformance with Rule J, Subsection 3.1b.

Required Abstraction Depth (inches)	Required Abstraction Volume (cubic feet)	Provided Abstraction Depth (inches)	Provided Abstraction Volume (cubic feet)
1.1	2,200	1.1	2,276

Because the proposed stormwater reuse system requires consistent use at a specified rate to meet District water quality requirements via abstractions, performance monitoring for the site will be required to ensure that the project provides the proposed volume abstraction.

### Water Quality Management

Subsection 3.1.c of Rule J requires the Applicant provide volume abstraction in accordance with 3.1b or least 60 percent annual removal efficiency for total phosphorus (TP), and at least 90 percent annual

removal efficiency for total suspended solids (TSS) from site runoff, and no net increase in TSS or TP loading leaving the site from existing conditions. Because the BMPs proposed by the applicant provide more volume abstraction than is require by 3.1b and the engineer concurs with the modeling, the engineer finds that the proposed project is in conformance with Rule J, Subsection 3.1.c.

### Low floor Elevation

No structure may be constructed or reconstructed such that its lowest floor elevation is less than 2 feet above the 100-year event flood elevation of a waterbody or stormwater management facility. No stormwater management system may be constructed or reconstructed in a manner that brings the low floor elevation of an adjacent structure into noncompliance according to Rule J, Subsection 3.6.

The low floor elevation of the proposed building and the adjacent stormwater management feature are summarized below. The proposed project is in conformance with Rule J, Subsection 3.6.

Low Floor Elevation of Existing Building (feet)	100-year Event Flood Elevation of Stormwater Facility (feet)	Freeboard (feet)
971.78	965.89	5.89

### Maintenance

Subsection 3.7 of Rule J requires the submission of a maintenance plan. All stormwater management structures and facilities must be designed for maintenance access and properly maintained in perpetuity to assure that they continue to function as designed. The stormwater management facilities include the underground filtration system, sump manhole structures, the rainwater harvest and reuse system. The Applicant provided a draft maintenance and inspection declaration for review by RPBCWD staff prior to recordation. To conform to the RPBCWD Rule J the following revisions are needed:

J1. Permit applicant must provide an updated maintenance and inspection declaration as required by Rule J, Subsection 3.7. The declaration must also include a stormwater reuse monitoring and reporting plan, including a map of the irrigation area. A revised draft declaration must be provided for District review and approval prior to recordation as a condition of issuance of the permit.

### Chloride Management

Subsection 3.8 of Rule J requires the submission of chloride management plan that designates the individual authorized to implement the chloride management plan and the Minnesota Pollution Control Agency-certified salt applicator engaged in implementing the plan. The permit applicant submitted an unsigned chloride management plan that designates Cory Zitzloff as the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in

implementing the plan at the site. However, chloride management plan submitted does not indicated the class information or provide evidence that Cory Zitzloff is an MPCA-certified salt applicator. To close out the permit and release the \$5,000 in financial assurance held for the purpose of chloride management, the permit applicant must provide a signed chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.

### Wetland Protection

Because the existing storm sewer system conveys runoff from the proposed stormwater management facilities to the on-site wetland, the project must comply with the wetland protection criteria in Rule J, Subsection 3.10. Subsection 3.10 of Rule J requires that the activity subject to this rule not alter a site in a manner that alters the bounce in water level, duration of inundation, or change the runout elevation beyond those specified in Table J1. Rather than conduct a MNRAM for the onsite wetland, the applicant elected to demonstrate compliance with the criteria for discharging to an exceptional value wetland. The following table summarizes the allowable change in bounce and inundation duration from Table J1 of RPBCWD Rule J.

Wetland Value/ Waterbody	Permitted Bounce for, 10-Year Event	Inundation Period for 1- and 2-Year Event	Inundation Period for 10-Year Event	Runout Control Elevation
Exceptional	Existing	Existing	Existing	No change

The Applicant used a HydroCAD hydrologic model to simulate runoff rates and flow depths for pre- and post-development conditions (phase 1 and phase 2) for applicable storm events specified in Table J1. Rule J, Subsection 3.10 identifies the permitted bounce for an exceptional value wetland must match the existing bounce for the 10-year event. The table below shows that the proposed design result in the same 10-year high water elevation for existing and proposed conditions, thus there is no change in the 10-year bounce and the project meets the bounce criteria for discharge to an exceptional value wetland.

10- Year Elevation (ft)					
Existing	Proposed				
946.5	946.5				

The HydroCAD model output hydrographs indicate that the proposed condition does not increase inundation in the wetland. Table J1 identifies the inundation period for 1-, 2-, and 10-year events for an exceptional value wetland must not exceed existing conditions. As shown in the table below, the submitted hydrologic models demonstrate that the duration of inundation has not been increased from existing conditions. The submitted materials demonstrate, and RPBCWD engineers concurs, that project is in conformance with Rule J, Subsection 3.10a.

2-Year Inundation Period (hrs)		10-Year Ir Period	nundation d (hrs)	100-Year Inundation Period (hrs)		10-Day Snowmelt Inundation Period (hrs)	
Ex	Prop	Ex	Prop	Ex	Prop	Ex	Prop
65	65	65	65	65	65	280	280

Rule J, Subsection 3.10b requires that for exceptional value wetlands, the project must meet at least 75 percent annual removal efficiency for phosphorus and at least 90 percent annual removal efficiency for total suspended solids. The Applicant is proposing the construction of an underground filtration system combined with a rainwater harvest and reuse system to provide volume abstraction and water quality treatment. The applicant used P8 to estimate the TP and TSS reduction provided by the underground filtration system. The resulting TP and TSS percent reductions by the underground filtration system were incorporated into the Minimal Impact Design Standards calculator to estimate the total treatment provided by the underground filtration system in combination with the rainwater harvest and reuse system. The results of this modeling are summarized in tables below showing the annual TSS and TP removal requirements are achieved prior to discharge entering the onsite wetland. The engineer concurs with the modeling, and finds that the proposed project is in conformance with Rule J, Subsection 3.10b.

Annual TSS and TP removal summary

Pollutant of Interest	Regulated Site Loading (lbs/yr)	Required Load Removal (lbs/yr)	Provided Load Reduction (lbs/yr)	
Total Suspended Solids (TSS)	219	197 (90%)	216 (99%)	
Total Phosphorus (TP)	1.21	0.91 (75%)	0.97 (78%)	

### Rule L: Permit Fee Deposit:

The RPBCWD permit fee schedule adopted in February 2020 requires permit applicants to deposit \$3,000 to be held in escrow and applied to cover the \$10 permit-processing fee and reimburse RPBCWD for permit review and inspection-related costs and when a permit application is approved, the deposit must be replenished to the applicable deposit amount by the applicant before the permit will be issued to cover actual costs incurred to monitor compliance with permit conditions and the RPBCWD Rules. A permit fee deposit of \$3,000 was received on September 26, 2024. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. Subsequently, if the costs of review, administration, inspections and closeout-related or other regulatory activities exceed the fee deposit amount, the applicant will be required to replenish the deposit to the original amount or such lesser amount as the RPBCWD administrator deems sufficient within 30 days of receiving notice that such deposit is due. The administrator will close out the relevant application or permit and revoke prior approvals, if any, if the permit-fee deposit is not timely replenished.

The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. As of October 29, 2024 the amount due is \$1,272.

### Rule M: Financial Assurance:

	Unit	Unit Cost	# of Units	Total
Rule C: Erosion Control				
Silt Fence	LF	\$2.50	375	\$938
Inlet Protection	EA	\$100	5	\$500
Rock Entrance	EA	\$250	1	\$250
Restoration of disturbance	Ac	\$2,500	0.69	\$1,725
Rule J: Stormwater Management Underground filtration system, sump manhole structures, the rainwater harvest and reuse system: 125% of engineer's opinion of cost (\$374,009*1.25)	EA	125% OPC	1	\$467,511
Chloride Management Plan	LS	\$5,000	1	\$5,000
Contingency (10%)		10%		\$47,592
Total Financial Assurance				\$523,516

**Applicable General Requirements:** 

- 1. The RPBCWD Administrator and Engineer shall be notified at least three days prior to commencement of work.
- 2. Construction must be consistent with the plans, specifications, and models that were submitted by the applicant that were the basis of permit approval. The date(s) of the approved plans, specifications, and modeling are listed on the permit. The grant of the permit does not in any way relieve the permittee, its engineer, or other professional consultants of responsibility for the permitted work.
- 3. The grant of the permit does not relieve the permittee of any responsibility to obtain approval of any other regulatory body with authority.
- 4. The issuance of this permit does not convey any rights to either real or personal property, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state, or local laws or regulations.
- 5. In all cases where the doing by the permittee of anything authorized by this permit involves the taking, using or damaging of any property, rights or interests of any other person or persons, or of any publicly owned lands or improvements or interests, the permittee, before proceeding therewith, must acquire all necessary property rights and interest.
- 6. RPBCWD's determination to issue this permit was made in reliance on the information provided by the applicant. Any substantive change in the work affecting the nature and extent of applicability of RPBCWD regulatory requirements or substantive changes in the methods or

means of compliance with RPBCWD regulatory requirements must be the subject of an application for a permit modification to the RPBCWD.

7. If the conditions herein are met and the permit is issued by RPBCWD, the applicant, by accepting the permit, grants access to the site of the work at all reasonable times during and after construction to authorized representatives of the RPBCWD for inspection of the work.

### **Findings**

- 1. The proposed project includes the information necessary, plan sheets and erosion control plan for review.
- 2. The proposed project will conform to Rules C and J if the Rule Specific Permit Conditions listed above are met.

### **Recommendation:**

Approval, contingent upon:

- 1. Financial Assurance in the amount of \$523,516.
- 2. Permit applicant must provide the name and contact information of the general contractor responsible for the site. RPBCWD must be notified if the responsible party changes during the permit term.
- Receipt in recordation a maintenance declaration for the stormwater management facilities. The declaration must also include a stormwater reuse monitoring and reporting plan, including a map of the irrigation area. Drafts of the declaration must be approved by the District prior to recordation.
- 4. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. The amount needed to replenish the permit fee deposit is \$1,272 as of October 29, 2024.
- 5.

By accepting the permit, when issued, the applicant agrees to the following stipulations:

- 1. Continued compliance with General Requirements
- 2. Per Rule J Subsection 4.5, upon completion of the site work, the permittee must submit as-built drawings demonstrating that at the time of final stabilization, the pretreatment manholes and subsurface stormwater facility and reuse system conform to design specifications and function as intended and approved by the District. As-built/record drawings must be signed by a professional engineer licensed in Minnesota and include, but not limited to:
  - a. the surveyed bottom elevations, water levels, and general topography of all facilities;
  - b. the size, type, and surveyed invert elevations of all stormwater facility inlets and outlets;
  - c. the surveyed elevations of all emergency overflows including stormwater facility, street, and other;

- d. other important features to show that the project was constructed as approved by the Managers and protects the public health, welfare, and safety.
- 3. Providing the following additional close-out materials:
  - a. Documentation that constructed filtration facilities perform as designed. This may include filtration testing, flood testing, or other with prior approval from RPBCWD.
  - b. Documentation that disturbed pervious areas remaining pervious have been decompacted per Rule C.2c criteria.
- 4. To close out the permit and release the \$5,000 in financial assurance held for the purpose of the chloride management, the permit applicant must provide a signed chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.



# **Construction Documents** for **Biolyph Parking Lot Expansion** Chaska, Minnesota Presented by: Martin Woody Architects

### CONSULTANT CONTACT LIST:

DEVELOPER/OWNER BIOLYPH 4275 NOREX DRIVE CHASKA, MN 55318 TEL 612-382-2423 CONTACT: TIMOTHY PEARCY

ARCHITECT **EDWARD FARR ARCHITECTS INC** 7710 GOLDEN TRIANGLE DRIVE EDEN PRAIRIE MN 55344 TEL 952-943-9660 CONTACT: ED FARR

GEOTECHNICAL NORTHERN TECHNOLOGIES INC 1408 NORTHLAND DRIVE #107 MENDOTA HEIGHTS, MN 55120 TEL 651-389-4191 FAX 651-389-4190 CONTACT: RYAN MENTER

Oct 10, 2024 - 9:21am - User:astutz L:\PROJECTS\20068.01\CAD\Civil\Sheets\20068.01-C1-TITLE.dwg

**CIVIL ENGINEER** SAMBATEK 12800 WHITEWATER DRIVE, SUITE 300 MINNETONKA, MN 55343 TEL 763-476-6010 FAX 763-476-8532 CONTACT: BRADY BUSSELMAN

SURVEYOR SAMBATEK 12800 WHITEWATER DRIVE, SUITE 300 MINNETONKA, MN 55343 TEL 763-476-6010 FAX 763-476-8532 CONTACT: MARK SALO

LANDSCAPE ARCHITECT SAMBATEK 12800 WHITEWATER DRIVE, SUITE 300 MINNETONKA, MN 55343 TEL 763-476-6010 FAX 763-476-8532 CONTACT: JOHNNIE WORKMAN



VICINITY MAP NO SCALE

SHEET INDEX									
SHEET	DESCRIPTION								
C1.01	TITLE SHEET								
C2.01	EXISTING CONDITIONS								
C3.01	SITE PLAN								
C4.01	GRADING AND EROSION CONTROL PLAN								
C4.02	EROSION CONTROL NOTES AND DETAILS								
C6.01	UTILITY PLAN								
C9.01	DETAILS								
L1.01	LANDSCAPE PLAN								
L1.02	LANDSCAPE DETAILS AND NOTES								



Project BIOLYPH **PARKING LOT EXPANSION** 

# Location CHASKA, MN

4275 NOREX DRIVE

### Certification

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly licensed professional ENGINEER under the laws of the state of Minnesota.

Brady D. Busselman Registration No. 44579 Date: 9/24/2024 If applicable, contact us for a wet signed copy of this plan which is available upon request at Sambatek's, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page: Phase: CD Initial Issued: 9/24/2024

**Revision History** No.Date By Submittal / Revision WATERSHED COMMENTS 10/10/2024

Sheet Title TITLE SHEET





### EEGEND ● FOUND MONUMENT ⋈──── I ─── - WATERMAIN – – – – EASEMENT LINE O SET MONUMENT O<sup>CO</sup> ▷ S SANITARY SEWER MARKED LS 47481 Image: Discourse of the second secon – · — · — · – SETBACK LINE ── △ ── RESTRICTED ACCESS ☑ ELECTRIC METER S→→ → FLARED END SECTION = CONCRETE CURB lpha light AC AIR CONDITIONER CO-UT -T TELEPHONE PEDESTAL ----- BUILDING CANOPY $\leftarrow$ GUY ANCHOR © UG – O GAS METER HANDICAP STALL ----- OW ----- OVERHEAD WIRE Q UTILITY POLE ------ CHAIN LINK FENCE POST IRON FENCE DECIDUOUS TREE $\{\circ\}$ ⊥ – SIGN ------ WOOD FENCE $\rightarrow$

### SURVEY NOTES =

- 1. The bearing system is based on the Carver County coordinate system, NAD83 (2011 Adjust). With an assumed bearing of South 89 degrees 16 minutes 50 seconds East for the North line of Lot 2, Block 1, Arbor Park 3rd Addition.
- The vertical datum is based on NAVD88. The originating bench marks is MNDOT JON, referenced from the MnDOT Geodetic Database BENCHMARK #1

Top nut of hydrant on west side of Norex Drive . Elev.=960.24

BENCHMARK #2 Top nut of hydrant in parking lot south of building. Elev.=971.28

3. Subject property's address is 4275 Norex Drive, Chaska, MN, its property identification number is 300540020.

### **SUBJECT PROPERTY**

Description from title commitment: Lot 2, Block 1, Arbor Park 3rd Addition, Carver County, Minnesota.

Abstract Property

Referencing Title Commitment No. 38171, dated 02/27/2014, that Commercial Partners Title, LLC as agent for Old Republic National Title Insurance Agency has provided us, the following comments on easements etc., that the property is subject to in Schedule B, Section 2 thereof using the same numbering system as in said Section 2. Exception Items No's. 1-12 and 18 are not Survey related items.

- 13. Drainage and utility easement as shown on the recorded plat of Arbor Park, as partially vacated by Resolution No. 88-81 filed January 23, 1990, as Document No. 111619 file February 6, 1990, as Document No. 111981; and by Resolution No. 88-110 filed March 12, 1991, as Document No. 122232. Easements are shown on survey. The easement vacations do not affect the surveyed property.
- 14. Drainage and utility easement as shown on the recorded plat of Arbor Park 3rd Addition. Easements are shown on survey.
- 15. Terms and conditions of Easement for electric transmission line purposes in favor of The Minnesota Valley Electric cooperative dated November 30, 1937, filed June 20, 1938 in Book 43 of deeds, Page 67. Easement is shown on survey.
- 16. Terms and conditions of Easement Agreement for drainage and ditch purposes dated August 18, 1956, filed August 18, 1956 in Book 61 of Deeds, Page 204. This item is not plotted hereon because it does not affect the subject property.
- 17. Terms and conditions of Grant of Easement for Conservation and Scenic Purposes dated March 1, 2005, filed March 18, 2005, as Document No. 410011. Easement is shown on survey.



**BITUMINOUS SURFACE** CONCRETE SURFACE LANDSCAPE SURFACE CONIFEROUS TREE



Eden Prairie MN 55344

# Project BIOLYPH **PARKING LOT** EXPANSION



4275 NOREX DRIVE



10/10/2024 WATERSHED COMMENTS

No.Date By Submittal / Revision

Sheet Title EXISTING CONDITIONS







🕨 www.sambatek.con 12800 Whitewater Drive, Suite 300 Minnetonka, MN 55343 763.476.6010 telephone 763.476.8532 facsimile Engineering | Surveying | Planning | Environmental Client EDWARD FARR ARCHITECTS, INC

7710 Golden Triangle Drive Eden Prairie MN 55344

Project BIOLYPH **PARKING LOT** EXPANSION

# Location CHASKA, MN

4275 NOREX DRIVE

### Certification I hereby certify that this plan, specification or

report was prepared by me or under my direct supervision and that I am a duly licensed professional ENGINEER under the laws of the state of Minnesota.

111sollunan )Na/IU Brady D. Busselman Registration No. 44579 Date: 9/24/2024 If applicable, contact us for a wet signed copy of this plan which is available upon request at Sambatek's, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page: Phase: CD Initial Issued: 9/24/2024

**Revision History** No.Date By Submittal / Revision 10/10/2024 WATERSHED COMMENTS







PROPOSE	D EXISTING
CURB & GUTTER	
IP OUT GUTTER	<u> </u>
TORM SEWER D	
DRAINTILE +++ -	
UILDING	
ETAINING WALL	
VETLAND LIMITS	WL
REELINE	
POT ELEVATION	X X X
CONTOUR	
IP RAP	
OVERFLOW ELEV.	$\int \frac{1}{902.5}$ ST <sub>1</sub> 5
OIL BORINGS	
IMITS OF DISTURBANCE	
AREAS OF DECOMPACTION	
DIRECTION OF	
TEMPORARY DIVERSION	
CHECK DAM	
IMITS OF DRAINAGE	
BIO-ROLL	
NLET PROTECTION DEVICE 1	Ø IP-1
NLET PROTECTION DEVICE 2	Ø IP−2
EMPORARY STONE	
EMPORARY SEDIMENT BASIN	→( SB )→
TEMPORARY STORAGE AND PARKI	
EMPORARY STABILIZATION MEAS	

- 1. PROPOSED CONTOURS ARE TO FINISHED SURFACE ELEVATION. SPOT ELEVATIONS ALONG PROPOSED CURB DENOTE GUTTER GRADE.
- CONTRACTOR SHALL REVIEW PAVEMENT GRADIENT AND CONSTRUCT "GUTTER OUT" WHERE WATER DRAINS AWAY FROM CURB. ALL OTHER AREAS SHALL BE CONSTRUCTED AS "GUTTER IN" CURB. ALL GRADIENT ON SIDEWALKS ALONG THE ADA ROUTE SHALL HAVE A MAXIMUM LONGITUDINAL SLOPE OF 5% (1:20), EXCEPT AT CURB RAMPS (1:12), AND A MAXIMUM CROSS SLOPE OF 2.08% (1:48). MAXIMUM SLOPE IN ANY DIRECTION ON AN ADA PARKING STALL OR ACCESS AISLE SHALL BE IN 2.08% (1:48). CONTRACTOR SHALL REVIEW AND VERIFY THE GRADIENT IN THE FIELD ALONG THE ADA ROUTES PRIOR TO PLACING CONCRETE OR BITUMINOUS. CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF THERE IS A DISCREPANCY BETWEEN THE GRADIENT IN THE FIELD VERSUS THE DESIGN GRADIENT. COORDINATE ALL WORK WITH PAVING CONTRACTOR.
- 4. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO AVOID PROPERTY DAMAGE TO ADJACENT PROPERTIES DURING THE CONSTRUCTION PHASES OF THIS PROJECT. CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGES TO THE ADJACENT PROPERTIES OCCURRING DURING THE CONSTRUCTION PHASES OF THIS PROJECT.
- SAFETY NOTICE TO CONTRACTORS: IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS ON THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE DUTY OF THE ENGINEER OR THE DEVELOPER TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON OR NEAR THE CONSTRUCTION SITE.
- CONTRACTOR SHALL COMPLETE THE SITE GRADING CONSTRUCTION IN ACCORDANCE WITH THE REQUIREMENTS OF THE OWNER'S SOILS ENGINEER. ALL SOIL TESTING SHALL BE COMPLETED BY THE OWNER'S SOILS ENGINEER. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED SOIL TESTS AND INSPECTIONS WITH THE SOILS ENGINEER. A GEOTECHNICAL ENGINEERING SOILS REPORT HAS BEEN COMPLETED BY:

COMPANY: NORTHERN TECHNOLOGIES, INC. ADDRESS: 1408 NORTHLAND DRIVE #107, MENDOTA HEIGHTS, MN 55120 PHONE: 651-389-4191 DATED: 6-5-2014

CONTRACTOR SHALL OBTAIN A COPY OF THE SOILS REPORT.

GRADING NOTES :

- 7. CONTRACTOR SHALL COMPLETE DEWATERING AS REQUIRED TO COMPLETE THE SITE GRADING CONSTRUCTION. PRIOR TO PLACEMENT OF THE AGGREGATE BASE, A TEST ROLL SHALL BE PERFORMED ON THE STREET AND PARKING AREA SUBGRADE. CONTRACTOR SHALL PROVIDE A LOADED TANDEM AXLE TRUCK WITH A GROSS WEIGHT OF 25 TONS. THE TEST ROLLING SHALL BE AT THE DIRECTION OF THE SOILS ENGINEER AND SHALL BE COMPLETED IN AREAS AS DIRECTED BY THE SOILS ENGINEER. CORRECTION OF THE SUBGRADE SOILS SHALL BE COMPLETED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SOILS ENGINEER.
- REPLACE ALL SUBGRADE SOIL DISTURBED DURING THE CONSTRUCTION THAT HAVE BECOME UNSUITABLE AND WILL NOT PASS A TEST ROLL. REMOVE UNSUITABLE SOIL FROM THE SITE AND IMPORT SUITABLE SOIL AT NO ADDITIONAL COST TO THE OWNER.
- 10. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING VEHICULAR AND PEDESTRIAN TRAFFIC CONTROL DEVICES SUCH AS BARRICADES, WARNING SIGNS, DIRECTIONAL SIGNS, FLAGMEN AND LIGHTS TO CONTROL THE MOVEMENT OF TRAFFIC WHERE NECESSARY. TRAFFIC CONTROL DEVICES SHALL CONFORM TO APPROPRIATE MINNESOTA DEPARTMENT OF TRANSPORTATION STANDARDS.
- 1. EXISTING TREES AND OTHER NATURAL VEGETATION WITHIN THE PROJECT AND/OR ADJACENT TO THE PROJECT ARE OF PRIME CONCERN TO THE CONTRACTOR'S OPERATIONS AND SHALL BE A RESTRICTED AREA. CONTRACTOR SHALL PROTECT TREES TO REMAIN AT ALL TIMES. EQUIPMENT SHALL NOT NEEDLESSLY BE OPERATED UNDER NEARBY TREES AND EXTREME CAUTION SHALL BE EXERCISED WHEN WORKING ADJACENT TO TREES. SHOULD ANY PORTION OF THE TREE BRANCHES REQUIRE REMOVAL TO PERMIT OPERATION OF THE CONTRACTOR'S EQUIPMENT, CONTRACTOR SHALL OBTAIN THE SERVICES OF A PROFESSIONAL TREE TRIMMING SERVICE TO TRIM THE TREES PRIOR TO THE BEGINNING OF OPERATION. SHOULD CONTRACTOR'S OPERATIONS RESULT IN THE BREAKING OF ANY LIMBS, THE BROKEN LIMBS SHOULD BE REMOVED IMMEDIATELY AND CUTS SHALL BE PROPERLY PROTECTED TO MINIMIZE ANY LASTING DAMAGE TO THE TREE. NO TREES SHALL BE REMOVED WITHOUT AUTHORIZATION BY THE ENGINEER. COSTS FOR TRIMMING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE GRADING CONSTRUCTION AND NO SPECIAL PAYMENT WILL BE MADE.
- L2. EXCAVATE TOPSOIL FROM AREAS TO BE FURTHER EXCAVATED OR REGRADED AND STOCKPILE IN AREAS DESIGNATED ON THE SITE. CONTRACTOR SHALL SALVAGE ENOUGH TOPSOIL FOR RESPREADING ON THE SITE AS SPECIFIED. EXCESS TOPSOIL SHALL BE PLACED IN EMBANKMENT AREAS, OUTSIDE OF BUILDING PADS, ROADWAYS AND PARKING AREAS. CONTRACTOR SHALL SUBCUT CUT AREAS, WHERE TURF IS TO BE ESTABLISHED, TO A DEPTH OF 6 INCHES. RESPREAD TOPSOIL IN AREAS WHERE TURF IS TO BE ESTABLISHED TO A MINIMUM DEPTH OF 6 INCHES. TOPSOIL SHALL CONTAIN AT LEAST 5% ORGANIC CONTENT, CONSISTENT WITH THE RILEY PURGATORY BLUFF CREEK WATERSHED DISTRICT DEFINITION.
- TRENCH BORROW CONSTRUCTION: IF ALLOWED BY THE OWNER, CONTRACTOR SHALL COMPLETE "TRENCH BORROW" EXCAVATION IN AREAS DIRECTED BY THE ENGINEER IN ORDER TO OBTAIN STRUCTURAL MATERIAL. TREES SHALL NOT BE REMOVED OR DAMAGED AS A RESULT OF THE EXCAVATION, UNLESS APPROVED BY THE ENGINEER. THE EXCAVATION SHALL COMMENCE A MINIMUM OF 10 FEET FROM THE LIMIT OF THE BUILDING PAD. THE EXCAVATION FROM THIS LIMIT SHALL EXTEND AT A MINIMUM SLOPE OF 1 FOOT HORIZONTAL TO 1 FOOT VERTICAL (1:1) DOWNWARD AND OUTWARD FROM THE FINISHED SURFACE GRADE ELEVATION. THE TRENCH BORROW EXCAVATION SHALL BE BACKFILLED TO THE PROPOSED FINISHED GRADE ELEVATION, AND SHALL BE COMPACTED IN ACCORDANCE WITH REQUIREMENTS OF THE QUALITY COMPACTION METHOD AS OUTLINED IN MN/DOT SPECIFICATION 2105.3F2. SNOW FENCE SHALL BE FURNISHED AND PLACED ALONG THE PERIMETER OF THE TRENCH BORROW AREA WHERE THE SLOPES EXCEED 2 FOOT HORIZONTAL TO 1 FOOT VERTICAL (2:1).
- 14. FINISHED GRADING SHALL BE COMPLETED, CONTRACTOR SHALL UNIFORMLY GRADE AREAS WITHIN LIMITS OF GRADING, INCLUDING ADJACENT TRANSITION AREAS. PROVIDE A SMOOTH FINISHED SURFACE WITHIN SPECIFIED TOLERANCES, WITH UNIFORM LEVELS OR SLOPES BETWEEN POINTS WHERE ELEVATIONS ARE SHOWN, OR BETWEEN SUCH POINTS AND EXISTING GRADES. AREAS THAT HAVE BEEN FINISHED GRADED SHALL BE PROTECTED FROM SUBSEQUENT CONSTRUCTION OPERATIONS, TRAFFIC AND EROSION. REPAIR ALL AREAS THAT HAVE BECOME RUTTED, ERODED OR HAS SETTLED BELOW THE CORRECT GRADE. ALL AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED TO EQUAL OR BETTER THAN ORIGINAL CONDITION OR TO THE REQUIREMENTS OF THE NEW WORK.
- 15. TOLERANCES. 15.a. THE COMMERCIAL BUILDING SUBGRADE FINISHED SURFACE ELEVATION SHALL NOT VARY BY MORE THAN 0.10 FOOT ABOVE, OR 0.10 FOOT BELOW, THE PRESCRIBED ELEVATION AT ANY POINT WHERE MEASUREMENT IS MADE.
- 15.b. THE STREET OR PARKING AREA SUBGRADE FINISHED SURFACE ELEVATION SHALL NOT VARY BY MORE THAN 0.05 FOOT ABOVE, OR 0.10 FOOT BELOW, THE PRESCRIBED ELEVATION OF ANY POINT WHERE MEASUREMENT IS MADE.
- 15.c. AREAS WHICH ARE TO RECEIVE TOPSOIL SHALL BE GRADED TO WITHIN 0.30 FOOT ABOVE OR BELOW THE REQUIRED ELEVATION, UNLESS DIRECTED OTHERWISE BY THE ENGINEER.
- 15.d. TOPSOIL SHALL BE GRADED TO PLUS OR MINUS 1/2 INCH OF THE SPECIFIED THICKNESS.
- 16. AFTER THE SITE GRADING IS COMPLETED, IF EXCESS OR SHORTAGE OF SOIL MATERIAL EXISTS, CONTRACTOR SHALL TRANSPORT ALL EXCESS SOIL MATERIAL OFF THE SITE TO AN AREA SELECTED BY THE CONTRACTOR, OR IMPORT SUITABLE MATERIAL TO THE SITE. 7. CONTRACTOR SHALL DETERMINE THE LOCATION OF ANY HAUL ROADS THAT MAY BE REQUIRED TO COMPLETE THE SITE GRADING CONSTRUCTION AND SHALL INDICATE HAUL ROADS ON EROSION AND SEDIMENT CONTROL "SITE MAP". CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE GOVERNING AUTHORITY OF EACH ROADWAY. CONTRACTOR SHALL POST WHATEVER SECURITY, AND COMPLY WITH ALL CONDITIONS WHICH ARE REQUIRED BY EACH GOVERNING AUTHORITY OF EACH ROADWAY.
- 18. CONTRACTOR SHALL SUBMIT AS-BUILT DRAWINGS TO RILEY PURGATORY BLUFF CREEK WATERSHED DISTRICT AT THE TIME OF FINAL STABILIZATION THAT DEMONSTRATE THE STORMWATER MANAGEMENT FACILITIES CONFORM TO THE APPROVED DESIGN.



THE SUBSURFACE UTILITY INFORMATION SHOWN ON THESE PLANS IS A UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF ASCE/CI 38-02, TITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA." THE CONTRACTOR AND/OR SUBCONTRACTORS SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. BY CONTACTING THE NOTIFICATION CENTER (GOPHER STATE ONE FOR MINNESOTA). THE ONTRACTOR AND/OR SUBCONTRACTOR AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES, WHICH MIGHT BE OCCASIONED BY HIS OR HER FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES (UNDERGROUND AND OVERHEAD). IF THE CONTRACTOR ENCOUNTERS ANY DRAIN TILE WITHIN THE SITE, HE OR SHE SHALL NOTIFY THE ENGINEER WITH THE LOCATION, SIZE, INVERT AND IF THE TILE LINE IS ACTIVE. NO DRAIN TILE SHALL BE BACKFILLED WITHOUT APPROVAL FROM THE PROJECT ENGINEER. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED MPROVEMENTS SHOWN ON THE PLANS.

12800 Whitewater Drive, Suite 300 Minnetonka, MN 55343 763.476.6010 telephone 763.476.8532 facsimile Engineering | Surveying | Planning | Environmenta

Client EDWARD FARR ARCHITECTS, INC 7710 Golden Triangle Drive

Eden Prairie MN 55344

Project BIOLYPH **PARKING LOT EXPANSION** 

# Location CHASKA, MN

4275 NOREX DRIVE

### Certification I hereby certify that this plan, specification or

report was prepared by me or under my direct supervision and that I am a duly licensed professional ENGINEER under the laws of the state of Minnesota.

Brady D. Busselman Registration No. 44579 Date: 9/24/2024 If applicable, contact us for a wet signed copy of this plan which is available upon request at Sambatek's, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page: Initial Issued: 9/24/2024 Phase: CD

**Revision History** No. Date By Submittal / Revisio 10/10/2024 WATERSHED COMMENTS

**Sheet Title GRADING AND** EROSION **CONTROL PLAN** 

Sheet No. Revision **C4.01** 





Oct 10, 2024 - 9:22am - User:astutz L:\PROJECTS\20068.01\CAD\Civil\Sheets\20068.01-C4-GRDE.dwg

PRE - CONSTRUCTION IMPERVIOUS	0.03 AC±
PROPOSED NEW IMPERVIOUS	0 52 AC+
	0.527.02
PROPOSED SEEDED AREA	0.17 AC±
TOTAL DISTURBED	0.69 AC±

CONSTRUCTION SEQUENCE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC	JAN	FEB	N
TEMPORARY CONTROL MEASURES															
STRIP & STOCKPILE TOPSOIL															
ROUGH GRADE / SEDIMENT CONTROL															
TEMPORARY CONSTRUCTION ROADS															
FOUNDATION / BUILDING CONSTRUCTION															
SITE CONSTRUCTION															
PERMANENT CONTROL STRUCTURES															
FINISH GRADING															
LANDSCAPING / SEED / FINAL STABILIZATION															
STORM FACILITIES															
NOTE: CONTRACTOR OR GENERAL CON	TRACTO	R TO O	OMPLE	ΤΕ ΤΑΙ	BLE WIT	Η ΤΗΕΙ	R SPEC	FIC PR	DJECT S	CHEDU	JLE				

	GENERAL EROSION NOTES:
1.	CONSTRUCTION SHALL COMPLY WITH ALL APPLICABLE GOVERNING CODES AND BE CONSTRUCTED TO SAME. WHERE A CONFLICT EXISTS BETWEEN LOCAL JURISDICTIONAL STANDARD SPECIFICATION AND SAMBATEK STANDARD SPECIFICATIONS, THE MORE STRINGENT SPECIFICATION SHALL APPLY.
2.	THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IS COMPRISED OF THIS DRAWING (EROSION & SEDIMENTATION CONTROL PLAN-ESC PLAN), THE STANDARD DETAILS, THE PLAN
3.	CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETING & SUBMITTING THE APPLICATION FOR THE MPCA GENERAL STORMWATER PERMIT FOR CONSTRUCTION ACTIVITY. ALL CONTRACTORS AND
	SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE SWPPP AND THE STATE OF MINNESOTA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH THE CONTENTS. THE SWPPP AND ALL OTHER RELATED DOCUMENTS MUST BE KEPT AT THE SITE DURING CONSTRUCTION.
4.	CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMP'S) AS REQUIRED BY THE SWPPP & PERMITS. CONTRACTOR SHALL OVERSEE THE INSPECTION & MAINTENANCE OF THE BMP'S
	AND EROSION PREVENTION FROM BEGINNING OF CONSTRUCTION AND UNTIL CONSTRUCTION IS COMPLETED, IS APPROVED BY ALL AUTHORITIES, AND THE NOTICE OF TERMINATION (NOT) HAS BEEN FILED WITH THE MPCA BY EITHER THE OWNER OR OPERATOR AS APPROVED ON PERMIT. ADDITIONAL BMP'S SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO ADDITIONAL DEPENDENT OF THE OWNER OF CONSTRUCTION AND UNTIL CONSTRUCTION ADDITIONAL BMP'S SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO ADDITIONAL DEPENDENT OF CONSTRUCTION.
5.	CONTRACTOR SHALL COMPLY WITH TRAINING REQUIREMENTS IN PART III.A.2 OF THE GENERAL PERMIT.
6.	BMP'S AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS
7	DIRECTED BY PERMITTING AGENCY OR OWNER.
	TIMES.
8.	CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE GENERAL PERMIT. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THE ESC PLANS SHALL BE CLEARLY DELINEATED (E.G. WITH FLAGS, STAKES, SIGNS, SILT FENCE, ETC.) ON THE DEVELOPMENT SITE BEFORE WORK BEGINS. GROUND DISTURBING ACTIVITIES MUST NOT OCCUR OUTSIDI THE LIMITS OF DISTURBANCE
9.	GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE
10	PARKING AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES.
	DISPOSED. NO ENGINE DEGREASING IS ALLOWED ON SITE.
11.	ALL LIQUID AND SOLID WASTES GENERATED BY CONCRETE WASHOUT OPERATIONS MUST BE CONTAINED IN A LEAK-PROOF CONTAINMENT FACILITY OR IMPERMEABLE LINER. A COMPACTED CLAY LINER IS NOT ACCEPTABLE. THE LIQUID AND SOLID WASTES MUST NOT CONTACT THE GROUND, AND THERE MUST NOT BE RUNOFF FROM THE CONCRETE WASHOUT OPERATIONS OR AREAS. LIQUID AND SOLID WASTES MUST BE DISPOSED OF PROPERLY AND IN COMPLIANCE WITH MPCA REGULATIONS. A SIGN MUST BE INSTALLED ADJACENT TO FACH WASHOUT FACILITY TO INFORM CONCRETE
40	EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES. SELF-CONTAINED CONCRETE WASHOUTS ON CONCRETE DELIVERY TRUCKS ARE ALLOWED.
12.	LEAKS.
13.	DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
14.	PROPERLY & MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS.
15.	HAZARDOUS MATERIALS: OIL, GASOLINE, PAINT & ANY HAZARDOUS SUBSTANCES MUST BE PROPERLY STORED, INCLUDING SECONDARY CONTAINMENT, TO PREVENT SPILLS, LEAKS OR OTHER DISCHARGE. RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE & DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MPCA
16.	ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE SWPPP, SHALL BE INITIATED AS SOON AS PRACTICABLE AND PRIOR TO SOIL DISTURBING ACTIVITIES
17	UPSLOPE.
17.	MN/DOT SEED MIXTURE NUMBER 21-111 OR 21-112 DEPENDING ON THE SEASON OF PLANTING (SEE MN/DOT SPECIFICATION SECTION 2575.3) SEEDING METHOD AND APPLICATION RATE SHALL CONFORM TO MN/DOT SPECIFICATION SECTION 2575.3. TEMPORARY MULCH SHALL BE APPLIED IN ACCORDANCE WITH MN/DOT SPECIFICATION SECTION 2575.3F1 AND 2575.3G. ALTERNATIVELY,
10	HYDRAULIC SOIL STABILIZER IN ACCORDANCE WITH MN/DOT SPECIFICATION SECTION 2575.3H MAY BE USED IN PLACE OF TEMPORARY MULCH.
18.	THE TIME TABLE DESCRIBED ABOVE. REFER TO THE GRADING PLAN AND/OR LANDSCAPE PLAN FOR VEGETATIVE COVER.
19.	CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT FROM CONVEYANCES & FROM TEMPORARY SEDIMENTATION BASINS THAT ARE TO BE USED AS PERMANENT WATER QUALITY MANAGEMENT BASINS. SEDIMENT MUST BE STABILIZED TO PREVENT IT FROM BEING WASHED BACK INTO THE BASIN, CONVEYANCES, OR DRAINAGEWAYS DISCHARGING OFF-SITE C TO SURFACE WATERS. THE CLEANOUT OF PERMANENT BASINS MUST BE SUFFICIENT TO RETURN THE BASIN TO DESIGN CAPACITY.
20.	ON-SITE & OFF-SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BMP'S. STOCKPILE AND BORROW AREA
21.	TEMPORARY SOIL STOCKPILES MUST HAVE SILT FENCE OR OTHER EFFECTIVE SEDIMENT CONTROLS & CANNOT BE PLACED IN SURFACE WATERS, INCLUDING STORMWATER CONVEYANCES SUCH AS
	CURB & GUTTER SYSTEMS OR CONDUITS & DITCHES.
22.	SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.
24	
24.	ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOU PAVING FOR ROAD CONSTRUCTION.
	MAINTENANCE NOTES:
ALL LON ON (	MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO IGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. THE DESIGNATED CONTACT PERSON NOTED ON THIS PLAN MUST ROUTINELY INSPECT THE CONSTRUCTION SITE ONCE EVERY SEVEN DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS. ALL EROSION AND SEDIMENTATION
CON	
1.	ALL SILT FENCES MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/3 OF THE HEIGHT OF THE FENCE. THESE REPAIRS MUST E MADE WITHIN 24 HOURS OF DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS.
2.	TEMPORARY AND PERMANENT SEDIMENTATION BASINS MUST BE DRAINED AND THE SEDIMENT REMOVED WHEN THE DEPTH OF SEDIMENT COLLECTED IN THE BASIN REACHES 1/2 THE STORAGE VOLUME. DRAINAGE AND REMOVAL MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS (SEE PART IV.D. OF THE GENERAL PERMIT).
3.	SURFACE WATERS, INCLUDING DRAINAGE DITCHES AND CONVEYANCE SYSTEMS, MUST BE INSPECTED FOR EVIDENCE OF SEDIMENT BEING DEPOSITED BY EROSION. CONTRACTOR MUST REMOVE AL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS. INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS, AND RESTABILIZE THE AREAS WHERE SEDIMENT REMOVAL
	RESULTS IN EXPOSED SOIL. THE REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN SEVEN (7) DAYS OF DISCOVERY UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL ACCESS CONSTRAINTS. CONTRACTOR SHALL USE ALL REASONABLE EFFORTS TO OBTAIN ACCESS. IF PRECLUDED, REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN SEVEN (7) CALENDAR DAYS OF
	OBTAINING ACCESS. CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AUTHORITIES AND RECEIVING ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK.
4.	CONSTRUCTION SITE VEHICLE EXIT LOCATIONS MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING ONTO PAVED SURFACES. TRACKED SEDIMENT MUST BE REMOVED FROM ALL OFF-SITE PAVED SURFACES, WITHIN 24 HOURS OF DISCOVERY, OR IF APPLICABLE, WITHIN A SHORTER TIME TO COMPLY WITH PART IV.C.6 OF THE GENERAL PERMIT.
5.	CONTRACTOR IS RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF TEMPORARY AND PERMANENT WATER QUALITY MANAGEMENT BMPS, AS WELL AS ALL EROSION PREVENTION AND SEDIMENT CONTROL BMPS, FOR THE DURATION OF THE CONSTRUCTION WORK AT THE SITE. THE PERMITTEE(S) ARE RESPONSIBLE UNTIL ANOTHER PERMITTEE HAS ASSUMED CONTROL (ACCORDING)
	TO PART II.B.5 OF THE MPCA GENERAL PERMIT) OVER ALL AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY STABILIZED OR THE SITE HAS UNDERGONE FINAL STABILIZATION, AND A (N.O.T.) HAS BEEN SUBMITTED TO THE MPCA.
6.	IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED IN A MANNER AND AT A FREQUENCY SUFFICIENT TO MINIMIZE OFF-SITE IMPACTS (E.G., FUGITIVE SEDIMENT IN STREETS COULD BE WASHED INTO STORM SEWERS BY THE NEXT RAIN AND/OR POSE A SAFETY HAZARD TO USERS OF PUBLIC STREETS).
7.	ALL INFILTRATION AREAS MUST BE INSPECTED TO ENSURE THAT NO SEDIMENT FROM ONGOING CONSTRUCTION ACTIVITIES IS REACHING THE INFILTRATION AREA AND THESE AREAS ARE PROTECTE
	FROM COMPACTION DUE TO CONSTRUCTION EQUIPMENT DRIVING ACROSS THE INFILTRATION AREA.
	RPBCWD NOTES:
1.	NATURAL TOPOGRAPHY AND SOIL CONDITIONS MUST BE PROTECTED, INCLUDING RETENTION ONSITE OF NATIVE TOPSOIL TO THE GREATEST EXTENT POSSIBLE.
2.	ADDITIONAL MEASURES, SUCH AS HYDRAULIC MULCHING AND OTHER PRACTICES AS SPECIFIED BY THE DISTRICT MUST BE USED ON SLOPES OF 3:1 (H:V) OR STEEPER TO PROVIDE ADEQUATE STABILIZATION.
3.	FINAL SITE STABILIZATION MEASURES MUST SPECIFY THAT AT LEAST SIX INCHES OF TOPSOIL OR ORGANIC MATTER BE SPREAD AND INCORPORATED INTO THE UNDERLYING SOIL DURING FINAL SITE TREATMENT WHEREVER TOPSOIL HAS BEEN REMOVED.
4.	CONSTRUCTION SITE WASTE SUCH AS DISCARDED BUILDING MATERIALS, CONCRETE TRUCK WASHOUT, CHEMICALS, LITTER AND SANITARY WASTE MUST BE PROPERLY MANAGED.
5.	ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE MAINTAINED UNTIL COMPLETION OF CONSTRUCTION AND VEGETATION IS ESTABLISHED SUFFICIENTLY TO ENSURE STABILITY C THE SITE, AS DETERMINED BY THE DISTRICT.
6.	ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE REMOVED UPON FINAL STABILIZATION.
7.	SOIL SURFACES COMPACTED DURING CONSTRUCTION AND REMAINING PERVIOUS UPON COMPLETION OF CONSTRUCTION MUST BE DECOMPACTED TO ACHIEVE:
7	7.1. A SOIL COMPACTION TESTING PRESSURE OF LESS THAN 1,400 KILOPASCALS OR 200 POUNDS PER SQUARE INCH IN THE UPPER 12 INCHES OF SOIL OR
/	V.2. A BOLK DENSITY OF LESS THAN 1.4 GRAMS PER COBIC CENTIMETER OR 87 POUNDS PER COBIC FOOT IN THE UPPER 12 INCHES OF SOIL. IN ADDITION, UTILITIES, TREE ROOTS AND OTHER EXISTING VEGETATION MUST BE PROTECTED UNTIL FINAL REVEGETATION OR OTHER STABILIZATION OF THE SITE.
8.	ALL DISTURBED AREAS MUST BE STABILIZED WITHIN 7 CALENDAR DAYS AFTER LAND-DISTURBING WORK HAS TEMPORARILY OR PERMANENTLY CEASED ON A PROPERTY THAT DRAINS TO AN IMPAIRED WATER, WITHIN 14 DAYS ELSEWHERE.
9.	THE PERMITTEE MUST, AT A MINIMUM, INSPECT, MAINTAIN AND REPAIR ALL DISTURBED SURFACES AND ALL EROSION AND SEDIMENT CONTROL FACILITIES AND SOIL STABILIZATION MEASURES EVERY DAY WORK IS PERFORMED ON THE SITE AND AT LEAST WEEKLY UNTIL LAND-DISTURBING ACTIVITY HAS CEASED. THEREAFTER. THE PERMITTEE MUST PERFORM THESE RESPONSIBILITIES AT
	LEAST WEEKLY UNTIL VEGETATIVE COVER IS ESTABLISHED. THE PERMITTEE WILL MAINTAIN A LOG OF ACTIVITIES UNDER THIS SECTION FOR INSPECTION BY THE DISTRICT ON REQUEST.
	SEQUENCE OF CONSTRUCTION
PH	ASE I:
1	
1. 2.	PREPARE TEMPORARY PARKING AND STORAGE AREA.
1. 2. 3. 4.	PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS.
1. 2. 3. 4. 5.	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPs. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH
1. 2. 3. 4. 5.	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPs. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND CRUB THE SITE
<ol> <li>1.</li> <li>2.</li> <li>3.</li> <li>4.</li> <li>5.</li> <li>6.</li> <li>7.</li> </ol>	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE.
<ol> <li>1.</li> <li>2.</li> <li>3.</li> <li>4.</li> <li>5.</li> <li>6.</li> <li>7.</li> <li>8.</li> </ol>	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES.
1. 2. 3. 4. 5. 6. 7. 8. PH/ 1.	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPs. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS.
1. 2. 3. 4. 5. 6. 7. 8. <b>PH</b> , 1. 2. 2	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS.
1. 2. 3. 4. 5. 6. 7. 8. PH/ 1. 2. 3. 4.	INSTALL STABILIZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL RIP RAP AROUND OUTLET STRUCTURES. INSTALL INLET PROTECTION AROUND ALL STORM SEWER STRUCTURES.
1. 2. 3. 4. 5. 6. 7. 8. PH/ 1. 2. 3. 4. 5. 6.	INSTALL STABILZED CONSTRUCTION ENTRANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL INLET PROTECTION AROUND ALL STORM SEWER STRUCTURES. PREPARE SITE FOR PAVING. PAVE SITE.
1. 2. 3. 4. 5. 6. 7. 8. PH, 1. 2. 3. 4. 5. 6. 7. 8	INSTALL STABILIZED CONTROCTION ENTRACES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SILT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL RIP RAP AROUND OUTLET STRUCTURES. INSTALL INLET PROTECTION AROUND ALL STORM SEWER STRUCTURES. PREPARE SITE FOR PAVING. PAVE SITE. INSTALL INLET PROTECTION AROUND ALL STORM SEWER STRUCTURES. PREPARE SITE FOR PAVING. PAVE SITE. INSTALL INLET PROTECTION DEVICES. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING
1. 2. 3. 4. 5. 6. 7. 8. <b>PH</b> 1. 2. 3. 4. 5. 6. 7. 8. 9.	INSTALL STABILIZED CONSTRUCTION DEVINGANCES. PREPARE TEMPORARY PARKING AND STORAGE AREA. CONSTRUCT THE SLIT FENCES ON THE SITE. CONSTRUCT THE SEDIMENTATION AND SEDIMENT TRAP BASINS. HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION. CLEAR AND GRUB THE SITE. BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. ASE II: TEMPORARILY SEED DENUDED AREAS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS. INSTALL INLET PROTECTION AROUND ALL STORM SEWER STRUCTURES. PREPARE SITE FOR PAVING. PAVE SITE. INSTALL INLET PROTECTION DEVICES. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF SITE IS STABILIZED), IF REQUIRED BY THE CONTRACT

ANTICIPATED APPROXIMATE TIMELINE:	
ESTIMATED PROJECT START DATE:	05/06/2021
ESTIMATED PROJECT COMPLETION DATE:	07/01/2021

### EROSION CONTROL MATERIALS QUANTITIES

ITEM	UNIT	QUANTI
SILT FENCE	LINEAR FEET	185
SILT DIKE	LINEAR FEET	190
BIO-ROLL	LINEAR FEET	0
CONSTRUCTION ENTRANCE	UNIT	1
INLET PROTECTION DEVICE (IP-1)	UNIT	2
INLET PROTECTION DEVICE (IP-2)	UNIT	2
INLET PROTECTION DEVICE (IP-3)	UNIT	1

٩R	APR	MAY	JUN
	•	•	

INC

D OF

NOUS 

'E ALL VAL

DING

ECTED

STING

TITY 

![](_page_16_Picture_37.jpeg)

Project BIOLYPH **PARKING LOT EXPANSION** 

7710 Golden Triangle Drive Eden Prairie MN 55344

# Location CHASKA, MN

4275 NOREX DRIVE

### Certification I hereby certify that this plan, specification or

report was prepared by me or under my direct supervision and that I am a duly licensed professional ENGINEER under the laws of the state of Minnesota.

Brady D. Busselman Registration No. 44579 Date: 9/24/2024 If applicable, contact us for a wet signed copy of this plan which is available upon request at Sambatek's, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page: Phase: CD Initial Issued: 9/24/2024

**Revision History** No. Date By Submittal / Revision 10/10/2024 WATERSHED COMMENTS

Sheet Title EROSION CONTROL **NOTES AND** DETAILS

![](_page_16_Picture_47.jpeg)

![](_page_17_Figure_0.jpeg)

![](_page_18_Figure_0.jpeg)

![](_page_18_Figure_1.jpeg)

Oct 10, 2024 - 9:22am - User:astutz L:\PROJECTS\20068.01\CAD\Civil\Sheets\20068.01-C9-DETL.dwg

![](_page_18_Figure_2.jpeg)

![](_page_19_Figure_0.jpeg)

REACE FI	LTRATIC	N SYSTEM					
PIPE DIA, IN (E)	ROWS (F)	PIPE INVERT (G)	BOTTOM OF ROCK (H)	BOTTOM OF SAND (K)	EDGE SPACING, IN (X)	PIPE SPACING, IN (S)	TOTAL STORAGE CF
42	11	962.90	962.90	960.70	18.0	22.7	13449.0

Oct 10, 2024 - 9:22am - User:astutz L:\PROJECTS\20068.01\CAD\Civil\Sheets\20068.01-C9-DETL.dwg

![](_page_19_Picture_4.jpeg)

7710 Golden Triangle Drive Eden Prairie MN 55344

# Project BIOLYPH **PARKING LOT EXPANSION**

# Location CHASKA, MN

4275 NOREX DRIVE

## Certification

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly licensed professional ENGINEER under the laws of the state of Minnesota.

/MSOllman ) Na M Brady D. Busselman Registration No.44579 Date: 9/24/2024 If applicable, contact us for a wet signed copy of this plan which is available upon request at Sambatek's, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page: Phase: CD Initial Issued: 9/24/2024

**Revision History** No.Date By Submittal / Revision 10/10/2024 WATERSHED COMMENTS

Sheet Title DETAILS

![](_page_19_Picture_15.jpeg)

![](_page_20_Figure_0.jpeg)

	PROPOSED	EXISTING		
PROPERTY LIMIT			STANDARD DUTY	
CURB & GUTTER			ASPHALT PAVING	
EASEMENT				
BUILDING				
RETAINING WALL				
WETLAND LIMITS		WL	CONCRETE SIDEWALK	
TREELINE				
LANDSCAPE EDING				
STORM SEWER	D			
SANITARY SEWER	<u>S</u> >	-(S)		
FORCEMAIN (SAN.)	<b>(IS</b> ) → FM <b>)</b>	- <u>(</u> S)		
WATERMAIN		<b>•</b>		
YARDDRAIN				
LIMITS OF DISTURBA	NCE — · · —			
TREE PROTECTION F	ENCE - TP -			
TREE TO BE REMOVE	ED 🚫			
SIGN				
PIPE BOLLARD				

### CITY LANDSCAPE CODE

N C C	NINIMUM SIZE R VERSTORY DECI ONIFEROUS TRE	UNDERSTORY DECIDUOUS TREE MAJOR SHRUB PLANTING	2" 5 GAL					
Т	OTAL CALIPER IN	NCHES	REQU	IRED: E	BASED	ON PF	EVIOUSLY APPROVED LANDSCAPE PLAN	
T T T	REE CALIPER REES REQ. REES PROP.	2.5" X 3	3.0" X -	3.5" X 5	4.0" X -	4.5"⊦ X 8		
Т	OTAL CALIPER IN	NCHES	PROP	OSED:			= 65 CAL. INCHES	
<u>U</u>	NDERSTORY/SH	RUBS			REQU	JIRED	PROPOSED	

58

### UNDERSTORY TREES SHRUBS

9.2.5.6 Screening and Landscaping Open parking areas containing six (6) or more parking spaces shall be screened on each side adjoining a residential or public use or a public street. [See Subsection 9.6.6.1(a).]

X

### PLANT SCHEDULE

PLANT SCH	EDULE	PARKING EXPANSION		
TREES	CODE	BOTANICAL / COMMON NAME	CONT	CAL
	NC	Catalpa speciosa / Northern Catalpa	B & B	2.5"Cal
	НВ	Celtis occidentalis / Common Hackberry	B & B	3"Cal.
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	IVV	Ostrya virginiana / American Hophornbeam	B & B	2.5"Cal
CONIFERS	CODE	BOTANICAL / COMMON NAME	CONT	CAL
	PA2	Picea abies / Norway Spruce	12` Ht.	Spade
	PPU	Picea pungens / Colorado Spruce	8` Ht.	Transplant
AND	PR2	Pinus resinosa / Red Pine	12` Ht.	Spade
A CONTRACTOR OF THE OWNER OWNER OF THE OWNER OWN	PS2	Pinus strobus / White Pine	12` Ht.	Spade
ORN. TREES	CODE	BOTANICAL / COMMON NAME	CONT	CAL
$\bigcirc$	SS	Malus x `Spring Snow` / Spring Snow Crab Apple	B & B	2"Cal
SHRUBS	CODE	BOTANICAL / COMMON NAME	CONT	
8	COA	Corylus americana / American Hazelnut	5 gal	
$\bigcirc$	вн	Diervilla Ionicera / Dwarf Bush Honeysuckle	5 gal	
(+)	CE	Euonymus alatus `Compactus` / Compact Burning Bush	5 gal	
	HAV	Hamamelis virginiana / Common Witch Hazel	10 gal	
	HA	Thuja occidentalis `Holmstrup` / Holmstrup Cedar	10 gal	
	VL	Viburnum lentago / Nannyberry	5 gal	
5	VTW	Viburnum trilobum `Wentworth` / Wentworth Cranberry Bush Viburnum	7 gal	
GROUND COVERS	CODE	BOTANICAL / COMMON NAME	CONT	
	TUR HIG	Turf Sod Highland Sod / Sod	Sod	

### EANDSCAPE KEY

(1A)(1B) TRANSPLANT EXISTING TREES WITH TREE SPADE AS FEASABLE FOR USE IN LANDSCAPE BUFFER  $\left< 2 \right>$  ROCK MULCH - 1<sup>1</sup>/<sub>2</sub>" RIVER ROCK MULCH @ 3" DEPTH OVER COMMERCIAL WEED BARRIER

![](_page_20_Picture_10.jpeg)

12800 Whitewater Drive, Suite 300 Minnetonka, MN 55343 763.476.6010 telephone 763.476.8532 facsimile Engineering | Surveying | Planning | Environmental Client EDWARD FARR

ARCHITECTS, INC 7710 Golden Triangle Drive Eden Prairie MN 55344

Project BIOLYPH **PARKING LOT** EXPANSION

Location CHASKA, MN

4275 NOREX DRIVE

QTY

QTY

QTY

QTY

5,162 sf

Certification

I hereby certify that this survey, plan or report was prepared by me or under my direct supervision and that I am a duly Licensed LANDSCAPE ARCHITECT under the laws of the State of Minnesota.

John R Workman Registration No. 59119 Date: 9/24/2024 This certification is not valid unless wet signed in blue ink. If applicable, contact us for a wet signed copy of this survey which is available upon request at Sambatek, Minnetonka, MN office.

Summary

Designed: AKF Drawn: JMW Approved: BDB Book / Page:

Phase: CD Initial Issued: 9/24/2024

**Revision History** No.Date By Submittal / Revision 10/10/2024 WATERSHED COMMENTS

Sheet Title LANDSCAPE PLAN

![](_page_20_Picture_24.jpeg)

![](_page_21_Figure_0.jpeg)

Oct 10, 2024 - 9:22am - User:astutz L:\PROJECTS\20068.01\CAD\Civil\Sheets\20068.01-L1-LAND.dwg

- ARCHITECT DISCREPANCIES WHICH MAY COMPROMISE THE DESIGN OR INTENT OF THE LAYOUT.
- 4. THE CONTRACTOR SHALL PROTECT EXISTING ROADS, CURBS/GUTTERS, TRAILS, TREES, LAWNS AND
- 5. LOCATE AND VERIFY ALL UTILITIES, INCLUDING IRRIGATION LINES, WITH THE OWNER FOR PROPRIETARY UTILITIES AND GOPHER STATE ONE CALL 48 HOURS BEFORE DIGGING. CONTRACTOR 22.5.
- THE LANDSCAPE ARCHITECT OF ANY CONFLICTS TO FACILITATE PLANT RELOCATION. 6. THE LANDSCAPE CONTRACTOR SHALL COORDINATE THE PHASES OF CONSTRUCTION AND
- THE CONTRACTOR SHALL REVIEW THE SITE FOR DEFICIENCIES IN SITE CONDITIONS WHICH MIGHT NEGATIVELY AFFECT PLANT ESTABLISHMENT, SURVIVAL OR WARRANTY. UNDESIRABLE SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT PRIOR TO
- QUANTITIES SHOWN IN THE PLANTING SCHEDULE ARE FOR THE CONTRACTOR'S CONVENIENCE.
- 10. EXISTING TREES AND SHRUBS TO REMAIN SHALL BE PROTECTED TO THE DRIP LINE FROM ALL CONSTRUCTION TRAFFIC, STORAGE OF MATERIALS ETC. WITH 4' HT. ORANGE PLASTIC SAFETY FENCING ADEQUATELY SUPPORTED BY STEEL FENCE POSTS 6' O.C. MAXIMUM SPACING.

- ANSI-Z60, LATEST EDITION, OF THE AMERICAN ASSOCIATION OF NURSERYMEN, INC. AND SHALL
- 5. ALL PLANTS MUST BE HEALTHY, VIGOROUS MATERIAL, FREE OF PESTS AND DISEASE AND BE
- 7. ALL TREES MUST BE STRAIGHT TRUNKED AND FULL HEADED AND MEET ALL REQUIREMENTS
- 8. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REJECT ANY PLANTS WHICH ARE DEEMED
- 9. NO SUBSTITUTIONS OF PLANT MATERIAL SHALL BE ACCEPTED UNLESS APPROVED IN WRITING BY
- CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE COVERAGE OF ALL PLANTING BEDS AT SPACING SHOWN AND ADJUSTED TO CONFORM TO THE EXACT CONDITIONS OF THE SITE. THE LANDSCAPE ARCHITECT SHALL APPROVE THE STAKING LOCATION OF ALL PLANT MATERIALS PRIOR
- 12. MULCH: DOUBLE SHREDDED HARDWOOD MULCH, CLEAN AND FREE OF NOXIOUS WEEDS OR OTHER DELETERIOUS MATERIAL, IN ALL MASS PLANTING BEDS AND FOR TREES, UNLESS INDICATED AS ROCK MULCH ON DRAWINGS. SUBMIT SAMPLE TO LANDSCAPE ARCHITECT PRIOR TO DELIVERY ON-SITE FOR APPROVAL. DELIVER MULCH ON DAY OF INSTALLATION. USE 3" FOR SHRUB BEDS, TREE RINGS, AND 3" FOR PERENNIAL/GROUND COVER BEDS, UNLESS OTHERWISE DIRECTED.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL MULCHES AND PLANTING SOIL QUANTITIES TO 4. ALL TREES SHALL HAVE SYMMETRICAL OR BALANCED BRANCHING ON ALL SIDES OF THE TREE.
- AND FOR EVERGREENS MOVED ANYTIME. APPLY AS PER MANUFACTURER'S INSTRUCTION. ALL EVERGREENS SHALL BE SPRAYED IN THE LATE FALL FOR WINTER PROTECTION DURING WARRANTY
- REMOVE WRAPPING AFTER MAY 1. TREE WRAPPING MATERIAL SHALL BE WHITE TWO-WALLED 17. ALL DECIDUOUS, PINE, AND LARCH PLANTINGS SHALL RECEIVE RODENT PROTECTION PER MNDOT
- 18. PLANTING SOIL FOR TREES, SHRUBS AND GROUND COVERS: FERTILE FRIABLE LOAM CONTAINING A LIBERAL AMOUNT (4% MIN.) OF HUMUS AND CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH. IT SHALL COMPLY WITH MNDOT SPECIFICATION 3877 TYPE B SELECT TOPSOIL. MIXTURE SHALL BE FREE FROM HARDPACK SUBSOIL, STONES, CHEMICALS, NOXIOUS WEEDS, ETC. SOIL MIXTURE SHALL HAVE A PH BETWEEN 6.1 AND 7.5 AND 10-0-10 FERTILIZER AT THE RATE OF 3 POUNDS PER CUBIC YARD. IN PLANTING BEDS INCORPORATE THIS MIXTURE THROUGHOUT THE ENTIRE BED IN A 6" LAYER AND ROTO-TILLING IT INTO THE TOP 12" OF SOIL AT A 1:1 RATIO.ANY PLANT STOCK NOT PLANTED ON DAY OF DELIVERY SHALL BE HEELED IN AND WATERED UNTIL INSTALLATION. PLANTS NOT
- WILL PERCOLATE PRIOR TO INSTALLING PLANTING MEDIUM AND PLANTS. THE CONTRACTOR SHALL FILL THE BOTTOM OF SELECTED HOLES WITH SIX INCHES OF WATER AND CONFIRM THAT THIS WATER WILL PERCOLATE WITHIN A 24-HOUR PERIOD. IF THE SOIL AT A GIVEN AREA DOES NOT DRAIN PROPERLY, A PVC DRAIN OR GRAVEL SUMP SHALL BE INSTALLED OR THE PLANTING
- 20. ALL PLANTS SHALL BE GUARANTEED FOR TWO COMPLETE GROWING SEASONS (APRIL 1 -

### REPLACEMENT INCLUDING LABOR AND PLANTS. 21. CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT AT LEAST 3 DAYS PRIOR TO PLANNED DELIVERY. THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT AT LEAST 24 HOURS IN ADVANCE OF BEGINNING PLANT INSTALLATION. 22. SEASONS/TIME OF PLANTING AND SEEDING: NOTE: THE CONTRACTOR MAY ELECT TO PLANT IN

- OFF-SEASONS ENTIRELY AT HIS/HER RISK. 22.1. POTTED PLANTS: 4/1 - 6/1; 9/21 - 11/1 DECIDUOUS /B&B 22.2. 4/1 - 6/1; 9/21 - 11/1 22.3. EVERGREEN POTTED PLANTS: 4/1 - 6/1; 9/21-11/1 22.4. EVERGREEN B&B: 4/1 - 5/1; 9/21 - 11/1 TURF/LAWN SEEDING 4/1 - 6/1; 7/20 - 9/20 22.6. NATIVE MIX SEEDING 4/15 - 7/20; 9/20-10/20 23. MAINTENANCE SHALL BEGIN IMMEDIATELY AFTER EACH PORTION OF THE WORK IS IN PLACE. PLANT MATERIAL SHALL BE PROTECTED AND MAINTAINED UNTIL THE INSTALLATION OF THE
- PLANTS IS COMPLETE, INSPECTION HAS BEEN MADE, AND PLANTINGS ARE ACCEPTED EXCLUSIVE OF THE GUARANTEE. MAINTENANCE SHALL INCLUDE WATERING, CULTIVATING, MULCHING, REMOVAL OF DEAD MATERIALS, RE-SETTING PLANTS TO PROPER GRADE AND KEEPING PLANTS IN A PLUMB POSITION. AFTER ACCEPTANCE, THE OWNER SHALL ASSUME MAINTENANCE RESPONSIBILITIES. HOWEVER, THE CONTRACTOR SHALL CONTINUE TO BE RESPONSIBLE FOR KEEPING THE TREES PLUMB THROUGHOUT THE GUARANTEE PERIOD. 24. ANY PLANT MATERIAL WHICH DIES, TURNS BROWN, OR DEFOLIATES (PRIOR TO TOTAL
- ACCEPTANCE OF THE WORK) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF THE SAME SPECIES, QUANTITY, AND SIZE AND MEETING ALL LANDSCAPE LEGEND SPECIFICATIONS. . WATERING: MAINTAIN A WATERING SCHEDULE WHICH WILL THOROUGHLY WATER ALL PLANTS
- ONCE A WEEK. IN EXTREMELY HOT, DRY WEATHER, WATER MORE OFTEN AS REQUIRED BY INDICATIONS OF HEAT STRESS SUCH AS WILTING LEAVES. CHECK MOISTURE UNDER MULCH PRIOR TO WATERING TO DETERMINE NEED. CONTRACTOR SHALL MAKE THE NECESSARY ARRANGEMENTS FOR WATER.

### TURF NOTES:

- FURF ESTABLISHMENT SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE PROVISIONS OF THE MN/DOT 2105 AND 2575 EXCEPT AS MODIFIED BELOW: ALL AREAS TO RECEIVE SOD SHALL ALSO RECEIVE 6" OF TOPSOIL PRIOR TO INSTALLING SOD. TOPSOIL SHALL BE FREE OF TREE ROOTS, STUMPS, BUILDING MATERIAL,
- AND TRASH, AND SHALL BE FREE OF STONES LARGER THAN 1 🖞 INCHES IN ANY DIMENSION. WHERE SOD ABUTS PAVED SURFACES, FINISHED GRADE OF SOD/SEED SHALL BE HELD 1" BELOW SURFACE ELEVATION OF TRAIL, SLAB, CURB, ETC.
- 3. SOD SHALL BE LAID PARALLEL TO THE CONTOURS AND SHALL HAVE STAGGERED JOINTS. ON SLOPES STEEPER THAN 3:1 OR IN DRAINAGE SWALES, SOD SHALL BE STAKED SECURELY. 4. TURF ON ALL OTHER AREAS DISTURBED BY CONSTRUCTION SHALL BE RESTORED BY SEEDING,
- MULCHING AND FERTILIZING. SEED MIXTURE NO.25-151 WILL BE PLACED AT THE RATE OF 120 POUNDS PER ACRE. ALL DISTURBED AREAS TO BE TURF SEEDED, ARE TO RECEIVE 6" TOP SOIL, SEED, MULCH, AND WATER UNTIL A HEALTHY STAND OF GRASS IS OBTAINED. FOR SLOPES STEEPER THAN 3:1 OR IN
- DRAINAGE SWALES INSTALL EROSION CONTROL BLANKET. ALL DISTURBED AREAS TO RECEIVE NATIVE SEED, ARE TO RECEIVE PLANTING SOIL, SEED, MULCH, AND WATER UNTIL A HEALTHY STAND OF GRASS IS OBTAINED. FOR SLOPES STEEPER THAN 3:1 OR IN DRAINAGE SWALES INSTALL EROSION CONTROL BLANKET.

### **GENERAL TREE SPECIFICATIONS:**

- ALL STREET AND PARKING LOT TREES SHALL BE LIMBED UP TO THE FOLLOWING HEIGHTS: 1.1. 2" CAL. TREES: LOWEST BRANCH 6' HT 1.2. 3" CAL.+ TREES: LOWEST BRANCH 7' HT. TREE CANOPY WIDTH SHALL BE RELATIVE TO HEIGHT/CALIPER OF TREE AND TYPE OF TREE.
- 2.1. 1" CALIPER/6-8' HT: 3-4' WIDTH MIN. 2.2. 2" CALIPER/12-14' HT: 4-5' WIDTH MIN.
- 2.3. 3" CALIPER/14-16' HT: 6-7' WIDTH MIN.
- CANOPY TREES SHALL NOT HAVE CO-DOMINATE LEADERS IN LOWER HALF OF TREE CROWN. TREES SHALL NOT BE TIPPED PRUNED.
- TREES SHALL BE FREE OF PHYSICAL DAMAGE FROM SHIPPING AND HANDLING. DAMAGED TREES SHALL BE REJECTED. SUMMER DUG TREES SHALL HAVE ROOTBALL SIZE INCREASED BY 20%
- TREES WHICH EXCEED RECOMMENDED CALIPER TO HEIGHT RELATIONSHIP SHALL BE REJECTED.

### **IRRIGATION NOTES:**

- 1. IRRIGATION SYSTEM TO BE DESIGN/BUILD. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR APPROVAL OF SYSTEM LAYOUT PRIOR TO INSTALLATION.
- ALL SOD TO RECEIVE SPRAY OR ROTOR IRRIGATION HEADS WITH MINIMUM DESIGN OF 1" **IRRIGATION PER WEEK.**
- ALL PLANT BEDS TO RECEIVE DRIP LINE IRRIGATION , WITH A MINIMUM DESIGN OF .25" IRRIGATION PER WEEK.
- PARKING ISLANDS TO BE IRRIGATED.

12800 Whitewater Drive, Suite 300 Minnetonka, MN 55343 763.476.6010 telephone 763.476.8532 facsimile Engineering | Surveying | Planning | Environmental

Client EDWARD FARR ARCHITECTS, INC 7710 Golden Triangle Drive

Eden Prairie MN 55344

Project BIOLYPH **PARKING LOT EXPANSION** 

# Location CHASKA, MN

4275 NOREX DRIVE

### Certification

I hereby certify that this survey, plan or report was prepared by me or under my direct supervision and that I am a duly Licensed LANDSCAPE ARCHITECT under the laws of the State of Minnesota.

John R Workman Registration No. 59119 Date: 9/24/2024 This certification is not valid unless wet signed in blue ink. If applicable, contact us for a wet signed copy of this survey which is available upon request at Sambatek, Minnetonka, MN office.

Summary Designed: AKF Drawn: JMW Approved: BDB Book / Page:

Phase: CD

Initial Issued: 9/24/2024

**Revision History** No.Date By Submittal / Revisior WATERSHED COMMENTS 10/10/2024

**Sheet Title** LANDSCAPE **DETAILS AND** NOTES

Sheet No. Revision L1.02

**Project No.** 20068.01

NOVEMBER 1), UNLESS OTHERWISE SPECIFIED. THE GUARANTEE SHALL COVER THE FULL COST OF